

What does a typical water service look like?

This figure shows the components of a typical water service in the City of Batavia.

1. Water Main – Typically cast iron or ductile iron pipe in the street or in the parkway.
2. Corporation Stop – A valve installed while tapping into the main.
3. Service Line – The line owned by the city that runs between the main and to the curb stop (see figure #5). Normally $\frac{3}{4}$ "", made of lead, copper, galvanized or poly.
4. Curb Valve Box – This is a cast iron box that allows access to the curb stop (see figure #5). This is owned by the City.
5. Curb Stop – A valve typically in the parkway, between the curb and the sidewalk. This is to shut the water off to the home. This is owned by the City.
6. Isolation Valves – A valve is required on the street side of the meter. There may be one on the house side of the meter but is not required.
7. Water Meter – The water meter is sized to match the size of your service and is installed by the City.
8. Property Line.
9. Responsibility of Property Owner – The property owner is responsible for maintaining the line past the curb stop and to the house.
10. Responsibility of the City – From the water main to the curb stop including the curb box, is the responsibility of the City to maintain

